

## SPANISH FORK CITY

### Sports Park Center 4 Plex Project – Pressurized Irrigation & Storm Drain, 2005

#### ***ADDENDUM #1***

***September 28, 2005***

**1. High Pressure Gas Main.** There is an existing high pressure gas main at station 9+22. All the storm drain from station 9+18 on shall be lowered 6 inches from what is shown on the plans to go under this gas main. Questar shall be notified at 324-3370 2 business days before any excavation work may be done around this gas main.

**2. 10 foot Paved Trail.** There is an existing 10 foot paved trail at station 0+10 that will have to be cut and repaved according to City Standards. The costs to do this shall be included in the cost of the 18 inch storm drain item.